

EL 844052935

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum)

M03763EPPC

Box No. I TITLE OF INVENTION	
LOCK	
Box No. II APPLICANT	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)	
Banham Patent Locks Limited 233-235 Kensington High Street LONDON W8 6SF United Kingdom	
<input type="checkbox"/> This person is also inventor.	
Telephone No.	
Facsimile No.	
Teleprinter No.	
State (that is, country) of nationality: United Kingdom	State (that is, country) of residence: United Kingdom
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input checked="" type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)	
COWPER, Brian Edward 114 Elm Road New Malden Surrey KT3 3HP United Kingdom	
This person is: <input type="checkbox"/> applicant only <input checked="" type="checkbox"/> applicant and inventor <input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)	
State (that is, country) of nationality: United Kingdom	State (that is, country) of residence: United Kingdom
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<input type="checkbox"/> Further applicants and/or (further) inventors are indicated on a continuation sheet.	
Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE	
The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: <input checked="" type="checkbox"/> agent <input type="checkbox"/> common representative	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)	
MOSEY, Stephen George and PEARCE, Anthony Richmond of Marks & Clerk, Alpha Tower, Suffolk Street Queensway, Birmingham, B1 1TT, United Kingdom	
Telephone No. 0121 643 5881	
Facsimile No. 0121 606 4766	
Teleprinter No.	
<input type="checkbox"/> Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.	

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ **AP** ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ **EA** Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP** European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA** OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)



National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> LC Saint Lucia |
| <input checked="" type="checkbox"/> AG Antigua and Barbuda | <input checked="" type="checkbox"/> LK Sri Lanka |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LR Liberia |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MA Morocco |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BG Bulgaria | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BZ Belize | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> MZ Mozambique |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CR Costa Rica | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> DM Dominica | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> DZ Algeria | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GD Grenada | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TZ United Republic of Tanzania |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> ZA South Africa |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | |
| <input checked="" type="checkbox"/> KR Republic of Korea | |
| <input checked="" type="checkbox"/> KZ Kazakhstan | |

Check-box reserved for designating States which have become party to the PCT after issuance of this sheet:



Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM					<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:			
		national application: country	regional application: regional Office	international application: receiving Office	
item (1) 11 March 2000	0005752.1	United Kingdom			
item (2)					
item (3)					
<input checked="" type="checkbox"/> The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): 1					
<small>* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.</small>					
Box No. VII INTERNATIONAL SEARCHING AUTHORITY					
Choice of International Searching Authority (ISA) <small>(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):</small>		Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority): Date (day/month/year) Number Country (or regional Office)			
ISA / EP					
Box No. VIII CHECK LIST; LANGUAGE OF FILING					
This international application contains the following number of sheets: request : 3 description (excluding sequence listing part) : 36 claims : 6 abstract : 1 drawings : 8 sequence listing part of description : Total number of sheets : 54		This international application is accompanied by the item(s) marked below: 1. <input checked="" type="checkbox"/> fee calculation sheet 2. <input type="checkbox"/> separate signed power of attorney 3. <input type="checkbox"/> copy of general power of attorney, reference number, if any: 4. <input type="checkbox"/> statement explaining lack of signature 5. <input type="checkbox"/> priority document(s) identified in Box No. VI as item(s): 6. <input type="checkbox"/> translation of international application into (language): 7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material 8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form 9. <input type="checkbox"/> other (specify):			
Figure of the drawings which should accompany the abstract: 19A		Language of filing of the international application: English			
Box No. IX SIGNATURE OF APPLICANT OR AGENT					
<small>Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).</small>					
 For and on behalf of BANHAM PATENT LOCKS LIMITED		 COWPER, Brian Edward			

For receiving Office use only	
1. Date of actual receipt of the purported international application: JC14 Rec'd PCT/PTO 09 OCT 2001	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:	
4. Date of timely receipt of the required corrections under PCT Article 11(2):	
5. International Searching Authority (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.

For International Bureau use only
Date of receipt of the record copy by the International Bureau:

PATENT COOPERATION TREATY

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference M037636PPC	FOR FURTHER ACTION see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.	
International application No. PCT/GB 01/ 00735	International filing date (day/month/year) 22/02/2001	(Earliest) Priority Date (day/month/year) 11/03/2000
Applicant BANHAM PATENT LOCKS LIMITED et al.		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 6 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

1. Basis of the report

a. With regard to the **language**, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

☐ the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing :

☐ contained in the international application in written form.

☐ filed together with the international application in computer readable form.

☐ furnished subsequently to this Authority in written form.

☐ furnished subsequently to this Authority in computer readable form.

☐ the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☐ the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. ☐ **Certain claims were found unsearchable** (See Box I).

3. ☐ **Unity of invention is lacking** (see Box II).

4. With regard to the **title**,

☒ the text is approved as submitted by the applicant.

☐ the text has been established by this Authority to read as follows:

5. With regard to the **abstract**,

☐ the text is approved as submitted by the applicant.

☒ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the **drawings** to be published with the abstract is Figure No.

☒ as suggested by the applicant.

☐ because the applicant failed to suggest a figure.

☐ because this figure better characterizes the invention.

19a

☐ None of the figures.

INTERNATIONAL SEARCH REPORT

International application No.

PCT/GB 01/ 00735

Box III TEXT OF THE ABSTRACT (Continuation of item 5 of the first sheet)

A lock for a door (10) comprises a casing (11), a bolt (55) operable to extend from or retract into the casing, a pivoted operating handle (36) operable at one side of the door to retract the bolt, lock means (28) for key operation at the other side of the door, and blocking means (81) to prevent operation of the handle to retract the bolt. In a locked closed position of the door, the bolt (55) is extended, and with the blocking means operated, key operation of the exterior lock means (28) both retracts the bolt and also de-actuates the blocking means. At the inside of the door further key operable lock means (39, 40) are provided solely to operate and, if required, to de-actuate, the blocking means.

INTERNATIONAL SEARCH REPORT

International application No.
PCT/GB 01/00735

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:

2. ☐ Claims Nos.:
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:

3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

see additional sheet

1. ☒ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.

2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.

3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:

4. ☐ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

Remark on Protest

- ☐ The additional search fees were accompanied by the applicant's protest.
- ☒ No protest accompanied the payment of additional search fees.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

This International Searching Authority found multiple (groups of) inventions in this international application, as follows:

1. Claims: 1-19

A lock for a wing where blocking means can be operated on one side of the wing such that retraction of the bolt by the operating member is prevented. Key operation of lock means on the other side of the wing allows retraction of the bolt and deactuation of said blocking means.

2. Claims: 20-31

A lock for a wing with a pivoting operating member on side of the wing to retract the bolt, a pivoting locking member to deadlock the bolt, and an element providing at least parts of bearing surfaces for a pivot of the operating member or of the locking member.

INTERNATIONAL SEARCH REPORT

International Application No

PCT/GB 01/00735

A. CLASSIFICATION OF SUBJECT MATTER

IPC 7 E05B13/00 E05B9/08 E05B63/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 E05B E05C

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 4 709 566 A (WILDENRADT CARL H) 1 December 1987 (1987-12-01) column 1, line 16 - line 23 column 3, line 44 - line 57 column 5, line 23 - line 59; figure ---	1,2,4-6, 19
X	US 2 651 934 A (ABRAHAM E. CHESLER) 15 September 1953 (1953-09-15) column 3, line 38 -column 5, line 67; figure ---	1-3
X	US 4 563 885 A (MADDEN ROY H) 14 January 1986 (1986-01-14) column 4, line 40 -column 5, line 9; figure --- -/--	1,19

☒ Further documents are listed in the continuation of box C.☒ Patent family members are listed in annex.

* Special categories of cited documents :

- "A" document defining the general state of the art which is not considered to be of particular relevance
- "E" earlier document but published on or after the international filing date
- "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- "O" document referring to an oral disclosure, use, exhibition or other means
- "P" document published prior to the international filing date but later than the priority date claimed

- "T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
- "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
- "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.
- "&" document member of the same patent family

Date of the actual completion of the international search

7 September 2001

Date of mailing of the international search report

18. 09. 2001

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Pieracci, A

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 5 794 467 A (JUSTICE RONNY E) 18 August 1998 (1998-08-18) column 4, line 19 - line 36; figure ---	1-3
A	US 4 732 418 A (CROWN MARLIN D ET AL) 22 March 1988 (1988-03-22) column 2, line 38 - line 47 column 3, line 55 -column 4, line 3; figures 3,4 ---	1,2,4
X	GB 2 268 221 A (PARKES JOSIAH & SONS LTD) 5 January 1994 (1994-01-05) page 5, line 25 -page 7, line 2; figures 3-5 ---	20,30
X	GB 2 142 688 A (BANHAM PATENT LOCKS LTD) 23 January 1985 (1985-01-23) the whole document ---	20,30
X	FR 2 626 307 A (LAPERCHÉ SA) 28 July 1989 (1989-07-28) page 4, line 33 -page 6, line 20; figure -----	20,30

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/GB 01/00735

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
US 4709566	A	01-12-1987	NONE	
US 2651934	A	15-09-1953	NONE	
US 4563885	A	14-01-1986	NONE	
US 5794467	A	18-08-1998	NONE	
US 4732418	A	22-03-1988	NONE	
GB 2268221	A	05-01-1994	NONE	
GB 2142688	A	23-01-1985	NONE	
FR 2626307	A	28-07-1989	NONE	

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
20 September 2001 (20.09.2001)

PCT

(10) International Publication Number
WO 01/69015 A2

(51) International Patent Classification⁷: E05B
(21) International Application Number: PCT/GB01/00735
(22) International Filing Date: 22 February 2001 (22.02.2001)
(25) Filing Language: English
(26) Publication Language: English
(30) Priority Data:
0005752.1 11 March 2000 (11.03.2000) GB

(81) Designated States (*national*): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CR, CU, CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

(71) Applicant (*for all designated States except US*): BAN-HAM PATENT LOCKS LIMITED [GB/GB]; 233-235 Kensington High Street, London W8 6SF (GB).


Published:

— without international search report and to be republished upon receipt of that report

(72) Inventor; and
(75) Inventor/Applicant (*for US only*): COWPER, Brian, Edward [GB/GB]; 114 Elm Road, New Malden, Surrey KT3 3HP (GB).
(74) Agents: MOSEY, Stephen, George et al.; Marks & Clerk, Alpha Tower, Suffolk Street Queensway, Birmingham B1 1TT (GB).

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: LOCK



(57) Abstract: A lock for a door (10) comprises a casing (11), a bolt (55) operable to extend from or retract into the casing, a pivoted operating handle (36) operable at one side of the door to retract the bolt, lock means (28) for key operation at the other side of the door, and blocking means (81) to prevent operation of the handle to retract the bolt. In a locked closed position of the door, the bolt (55) is extended, and with the blocking means operated, key operation of the exterior lock means (28) both retracts the bolt and also de-actuates the blocking means. At the inside of the door further key operable lock means (39, 40) are provided solely to operate and, if required, to de-actuate the blocking means. A casting (38) secured in the casing mounts the further lock means (39, 40), provides part-bearings (38b: 138b) for pivot rods (41, 43) of the handle (36) and a bolt locking element (44), provides a guide slot (138d) for a spring-like connector (49) linking the handle to the bolt locking element, and provides a pair of arms (66) between which slides a bolt release member (69) and against which bears one end of a biasing spring around part of the bolt release member.

WO 01/69015 A2

LOCK

This invention relates to a lock for a movable wing, and particularly to a lock intended to be rim fitted to a domestic entrance door.

An object of the invention is to provide such a lock in an improved form.

According to the invention a lock for a wing movable between respective open and closed positions relative to a frame comprises a casing, a bolt operable to extend from or to retract into said casing, an operating member arranged to be operable at one side of the wing, in use, to effect retraction of the bolt, lock means arranged, in use, for key operation at the other side of the wing, and blocking means operable, in use, to prevent operation of the operating member to retract the bolt, the arrangement being such that, in use, in a locked, closed position of the wing said bolt is extended and said blocking means, if operated, prevents retraction of the bolt by said operating member, key operation of said lock means de-actuating said blocking means, if operated.

Preferably the key operation of said lock means retracts the bolt.

More preferably said blocking means are operable, in use, from said one side only of the wing to prevent retraction of the bolt by the operating member. Conveniently said blocking means are operable to prevent retraction of said bolt by the operating member by key operable lock means at said one side of the wing. Desirably said key operable lock means are operable at said one

- 2 -

side of the wing also to de-actuate said blocking means. Advantageously said operating member is a pivotable handle and the blocking means is an angularly movable cam.

According to another aspect of the invention a lock for a wing movable between open and closed positions relative to a frame comprises a casing, a bolt operable to extend from or to retract into said casing, an operating member at one side of the wing, in use, arranged to be pivotally operable to retract the bolt, a pivoted locking member at least partly within the casing, arranged to deadlock the bolt when it is in its extended position, and an element providing within the casing either at least part of a bearing surface for a pivot of the operating member or a pivot of the locking member, or at least parts of respective bearing surfaces for respective pivots of the operating member and the locking member.

Preferably for each pivot, said element provides a semi-cylindrical bearing surface. Desirably each such semi-cylindrical bearing surface provided by said element mates with a corresponding semi-cylindrical bearing surface provided by the casing. Conveniently the element has a portion projecting outwardly through an opening of the casing, said portion receiving a lock cylinder and plug assembly. Advantageously said element is unitary, preferably a casting, for example of zinc based alloy.

The invention will now be described, by way of example, with reference to the accompanying drawings, in which:

- 3 -

Figure 1 is a schematic internal side view of a casing of a lock of the invention, with a bolt thereof in its normally retracted state and a handle in its rest position,

Figures 2 and 3 are respective views similar to Figure 1, showing the bolt partly and fully extended from the lock casing,

Figure 4 is a view corresponding to Figure 3, but with the handle partly pivoted from its rest position,

Figure 5 is a view corresponding to Figure 4, with the handle fully pivoted and the bolt in its normally retracted state,

Figure 6 is a schematic fragmentary, internal plan view of the lock casing, with the bolt in its fully extended, deadlocked state,

Figure 7 is a schematic fragmentary, internal view at 90° to Figure 6,

Figures 8 and 9 are views corresponding to Figures 6 and 7 respectively, but with the bolt in its normally retracted state,

Figure 10 is a view corresponding to Figures 6 and 8 showing a cam member in two alternative positions at the commencement and end of bolt retraction respectively by said cam member,

Figures 11 and 12 are views corresponding respectively to the two views of Figure 10,

- 4 -

Figure 13 is a simplified schematic internal side view of the lock casing showing a snib for locking the bolt in its retracted position, the bolt being shown in its normally retracted state prior to actuation of said snib,

Figure 14 is a view corresponding to Figure 13, but with the bolt retracted further into the casing and the snib actuated,

Figure 15 is a view corresponding to Figures 13 and 14, with the bolt in its normally retracted state and the snib actuated to lock the bolt,

Figure 16 is a fragmentary, schematic internal simplified, side view of the casing showing a spring loaded catch and associated bolt retention element,

Figure 17 is a fragmentary plan view corresponding to Figure 16, with the bolt retention element retaining the bolt in its normally retracted state,

Figure 18 is a view corresponding to Figure 17, but with the catch depressed to release the bolt retention element to allow the bolt to move to its extended position,

Figure 19A is a schematic, fragmentary side sectional view of the casing showing a key operated lock cylinder arranged at one side of the lock casing having been operated to cause movement of blocking means to a position to prevent operation of the handle to retract the bolt,

- 5 -

Figure 19B is a schematic, fragmentary, split part-sectional view showing how a rose around said lock cylinder of Figure 19B is secured to said one side of the casing,

Figure 19C is a schematic, split part-sectional view of the lock casing as in Figure 15, but showing the lock cylinder of Figure 19C,

Figure 20 is a diagrammatic plan view of the arrangement of Figure 19A,

Figures 21 and 22 show positions of the lock cylinder plug relative to the blocking member when the blocking member is moved clear of the handle, before the key turns the plug to the key removal position and after the plug has been turned respectively,

Figure 23 is a simplified internal plan view showing the fixing of the lock casing to one side and front edge surface of a door,

Figure 24 is a schematic reduced scale view similar to Figure 19, showing a housing which receives the lock cylinder in position to be fitted to the lock casing,

Figures 25 and 26 are schematic reduced scale views similar to Figures 3 and 2 respectively showing bearings for the bolt deadlock element and the handle, the handle not being shown in Figure 26,

Figure 27 is a scrap view of the housing in the direction of arrow A of Figure 24,

- 6 -

Figures 28 and 29 are opposite side views respectively of the housing of Figure 24,

Figure 30 is an interior plan view of a main body part of the lock casing when empty,

Figure 31 is a scrap side view of part of a locking assembly operable at the outside of the door, and

Figures 32a and 32b respectively show a bar of the locking assembly of Figure 31 engaged with the blocking member of Figures 19 to 22 in two positions.

Shown in the Figures is a lock of the invention, which in the illustrated embodiment is rim mounted, i.e. as shown in Figure 23, is intended to be mounted at one side and partly at one front edge surface of a wing such as a conventionally hinged door 10 which has an associated frame and staple (not shown) so that the door can be moved between an open position and a closed position in which it is locked by a bolt of the lock, such bolt being described hereinafter.

The lock has a metal casing made up of a main body part 11, in the general form of a square box structure having one side open, and a closure part 12 in the form of a flat square metal plate. The plate has respective holes at or adjacent each of its four corners for fixing screws passing into respective threaded bores in bosses formed with the body part 11, to secure part 12 in

- 7 -

place inwards of the plane of the outer free edge surface of the part 11, and to complete the lock casing with the assembled components therein concealed from view.

As mentioned, the main body part 11 is in the form of a square box-structure and Figure 23 shows a side wall 13 integrally formed with an end wall 14 and a front wall 15 which is extended from the side wall 13 further than the end wall 14 to form a forend of the lock, with the extension part of the wall 15 being secured to a front edge surface of the door 10 as shown in Figure 23, with the free edge surface of the end wall 14 engaging against the inner side of the door, in use, again as shown in Figure 23. The main body part 11 is completed by a bottom wall 16, and a parallel top wall 17 shown in Figures 17 and 18.

The extended part of the front wall 15 is formed with a spaced pair of countersunk holes adjacent its upper and lower edges respectively, one of which 18, is shown in Figure 23, these countersunk holes receiving corresponding screws, such as screw 19 shown in Figure 23, for securing this extension of the front wall 15 in a corresponding depth rebate in the front edge surface of the door 10. In the front wall 15, at a position just inward of the plane defined at the open side of part 11, are a pair of spaced countersunk holes, one of which 20 is shown in Figure 23. At substantially the same level from the side wall 13 as the countersunk holes 20 is provided on the interior of the end wall 14 an integral lug 21 which has a circular-section hole 22 therethrough, the plate 12 having a cut-out to accommodate the lug 21. The outer surface of the lug is spaced from the outer free edge surface of the body part 11 by the thickness of a flat mounting plate 12a. This lug 21 is

- 8 -

centrally disposed along the end wall 14, and the plate 12a has a tapped hole 23 adjacent one of its edges centrally along the length thereof, so that, as shown in Figure 23, with the plate 12a in place at the 'open' side of the main body part 11, the plate 12a can rest on the outer surface of the lug 21, at a position spaced from part 12, so as to lie flush at said 'open' side of the body part 11, with the hole 23 aligned with the hole 22 through the lug. Moreover, at its edge surface opposite to its edge surface adjacent which the hole 23 is provided, the plate has two integral bent down tags, one of which, 24, is shown in Figure 23. Each tag extends through a slot in part 12, and has a tapped hole therethrough this being shown as 25 for tag 24. With the plate 12a arranged, as described, flush at the outer 'open' side of the body part 11, the holes through the respective tags are aligned with the countersunk holes 20 to receive fixing screws, one of which, 26, is shown in Figure 23. In use, as shown in Figure 23, a screw 27, captive in the hole 22 in the lug, has its shank engaged in the aligned tapped hole 23 in the plate 12a, with its free end received in a recess in the side surface of the door. Accordingly in this way the completed casing, comprising the main body part 11 and part 12, is secured to the mounting plate 12a, and by way of the screws 19 the completed casing is also secured to part of the front edge surface of the door. The fixing of the plate 12a to part 11 is particularly convenient as compared to prior art arrangements where the equivalent component is often a complicated pressing with tags, slots and the like for securement to the lock case. The plate 12a has two countersunk fixing holes therein, one spaced above the other, for wood screws to fix it to the side of the door. One hole 12b is shown in Figure 23. The fixing of the screw 27 forms the subject of our UK Patent Application No. 0005755.4 from which

- 9 -

our co-pending International Patent Application No. (Our Ref: 37639M) claims priority.

Additionally as shown in Figure 23, the plate 12a has a lock cylinder and plug assembly 28 secured thereto. The assembly is positioned on the plate 12a centrally over a circular hole (not shown) in the plate 12a, with respective projections from the end of the cylinder at respective opposite sides of said hole in the plate 12a, extending into correspondingly shaped openings respectively in the plate 12a. To secure the assembly 28 in this located position on the plate 12a, the plate has a pair of spaced aligned holes 29 therethrough at opposite sides of the hole in the plate 12a at which the assembly is centred, and screws 30 are respectively engaged in the holes 29, with the shanks of said screws extending into respective threaded bores 31 in the cylinder of the assembly 28.

In use, as shown in Figure 23, the completed casing is secured to the door as shown, with the assembly 28 received in a circular-section opening through the door, the end of the assembly projecting from the other side of the door and having fixed therearound a rose 32 or equivalent member. The rose can have a pair of rearwardly directed bosses, arranged diametrically at the top and bottom of the assembly 28, and received in respective bores in the door, and these bosses can be aligned with respective bolts, one of which is shown in Figure 23 by the numeral 33, which extend through respective holes in the plate 12a, with the shanks of the bolts extending through the thickness of the door 10. In one arrangement the threaded ends of these bolts can be engaged in open threaded ends respectively of the rearwardly extending bosses of the rose 32 so as tightly to secure the rose to the outer surface of the door as

- 10 -

shown in Figure 23. With the arrangement described, therefore, and as shown in Figure 23, the lock casing is securely secured to one side of the door with its lock cylinder and plug assembly 28 secured through the door and accessible for operation at the opposite side thereof. Schematically shown in Figure 31 is a plug 28a and operating bar 28b of assembly 28.

A central edge part of the side wall 13 is provided with a rectangular opening 34 schematically as identified in Figure 23, and a communicating similar rectangular opening 35 is provided in the adjoining edge part of end wall 14. At opposite ends of the opening 34 the interior surface of side wall 13 is provided with respective concave semi-cylindrical bearing surfaces for pivotally mounting a handle 36 which extends through the openings 34 and 35, as will be described. The bearing surfaces 34a are identified in Figures 24, 26 and 30.

Disposed centrally in the side wall 13 and spaced a little way inwardly of the inner edge of the opening 34, is an oval hole 37 in which is fitted a housing 38 for a lock cylinder 39 and its associated plug 40 as shown in Figures 19 and 25. This housing 38 is in the form of a metal casting, e.g. of zinc based alloy, and also includes a pair of parallel spaced arms 38a which have respective concave semi-cylindrical bearing surfaces 38b defined therein as shown in Figures 24, 26 and 29. The bearing surfaces 38b mate with the corresponding bearing surfaces 34a to form a pair of spaced full bearings for a pivot rod 41 which is located in a part circular channel 42 (Figures 19A, 21, 22 and 23) adjacent an inner edge of the handle 36 so as to allow pivoting of the handle 36 relative to the casing. Respective opposite end portions of the rod 41 pass through respective opposite ends of the handle which close

- 11 -

the channel 42, and extend outside of said handle ends into said full bearings respectively. Full pivoting of the handle, as shown in Figures 5 and 23, is required to allow access through a cut-out 36a in the end of the handle, and through openings 34, 35, for a screwdriver shank 27a, to enable it to engage the screw 27 both on assembly of the lock casing to the door, or for removal.

The housing 38 also provides, adjacent said spaced arms thereof, respective fixing holes 38c therethrough, these holes being aligned with respective internally threaded bosses 13a upstanding from the inner surface of the side wall 13. By the use of fixing screws, the housing 38 is thereby secured to said side wall of the casing. This side wall has two holes 13c, 13d therethrough at respective opposite sides of the part of the housing which extends outwardly from said side wall 13, these holes being on a diameter through the centre of the lock cylinder 39 and its associated plug 40. The part of the housing 38 within the casing is provided with one hole 38d aligned with the hole 13c in the side wall 13 and also a cut-away 38e which is aligned with said other 13d of said diametrically aligned holes in the side wall 13. The shanks of respective headed fixing screws 38h (Figures 19B and 19C) are received through said holes 13c, 13d in the side wall 13, with the heads received in said hole 38d and cut-away 38e respectively. The respective threaded ends of these fixing screws are threadedly received in blind bores in the inner surface of a rose 110 which is fitted around the part of the housing 38 projecting outwardly of the casing, this rose being pulled by said fixing screws against the outer surface of the side wall 13 so as to conceal from view, and to prevent access to, a grub screw hole 38f with associated grub screw 38g, extending through the housing 38 at the exterior of the casing, this grub screw engaging in a recess in the outer side of the cylinder 39,

- 12 -

thereby to secure the cylinder, with its associated rotatable plug therein, to the housing 38. The respective posi-drive heads of these fixing screws extending through the casing part 11 to secure the rose in place are arranged to be uncovered and easily accessible within the casing part 11 when the assembly of casing part 11 and closure part 12 is removed from the plate 12a on the door in use, and with the bolt of the lock held retracted, without having to remove components of the lock from the casing part 11, thereby making cylinder removal and replacement much easier than with known arrangements. The plate 12 has holes 12c therein aligned with these fixing screws respectively. Once the casing part 11 is removed from the door, all that is required is an undoing of said uncovered fixing screws, the heads of which move into previously 'empty' parts of hole 38d and cut-away 38e, to release the rose 110, thereby uncovering the grub screw 38g. This is then undone, allowing the cylinder 39 and plug 40 to be changed at the outside of the casing part 11. The grub screw is then retightened, the rose replaced and the fixing screws tightened to secure the rose to the surface of side wall 13. This feature forms the subject of our UK Patent Application No. 0005753.9 from which our co-pending International Patent Application No. (Our Ref. 37637M) claims priority. On assembly the rose 110 can firstly be secured in place by screws 38h and the housing 38 secured in place thereafter.

The structure of the housing 38 within the casing, provides four further functions. Firstly, it has two further spaced arms 138a defining respective concave semi-cylindrical bearing surfaces 138b, the arms and the bearing surfaces being shown in Figures 24 to 29. The arms 138a extend away from the end wall 14 and the surfaces 138b are directed towards the interior

- 13 -

surface of the side wall 13 where said bearing surfaces 138b mate with corresponding respective concave semi-cylindrical bearing surfaces 13b formed on projections upstanding from the interior surface of the side wall 13. This pair of completed spaced bearings act as a pivoting arrangement for a rod 43 of a deadlock element 44 shown best in Figures 1 to 5, Figures 7 to 12, and Figures 25 and 26.

As shown in these Figures, the deadlock element has a rectangular body part 45 extending away from the rod 43, the part 45 having a downturned nose 46 at its end remote from the rod. At the longer side of the body part 45 facing the top wall 17, the body part has a U-shaped projection 47 which is open upwardly and outwardly. The lower interior surface of the projection 47 is substantially at the level of the underside of the body part 45, but at the location of this projection 47, the side of the body part has its lower portion recessed, as shown at 48, so as to receive, as will be described, a straight end part of a spring-like connecting member 49 which links the handle 36 to said deadlock element 44. A second function provided by the housing 38 is a provision of a pair of upstanding surfaces 138c which define between them a guide slot 138d for a further part 50 of the spring-like connecting member 49 which extends to co-act with the handle 36. As shown in Figures 1 to 5, the handle, at its side adjacent the top wall 17 has an arm 51 extending from said channel 42, this arm defining a nose part 52. At its inner side, spaced slightly downwardly from the top of the nose part 52, as viewed with the orientation of the nose part shown in Figures 1 to 3, is a further, smaller nose part 53, the parts 52 and 53 being spaced by a section defining a groove 54. This groove is to receive said further part 50 of the spring-like connecting

- 14 -

member 49, as shown in Figures 1 to 5, whilst the further nose part 53 is to engage an end of a bolt 55 of the lock, as will be described hereinafter.

As shown in Figures 1 to 5, the connecting member 49, which is of spring steel, has a central coiled part 56, which is received on the rod 43 which acts as the pivot for the deadlock element 44. At the end of the coiled part 56 remote from the top wall 17, the member is formed with a straight part 57, lying in a plane parallel to the walls 16 and 17, this having its end turned through 90° to provide the previously mentioned straight part which extends into the recessed portion 48 of the body part 45 of the deadlock element 44 as shown in Figures 1 to 5. At the other end of the coiled part 56, the further part 50 extends away from the side wall 13, through the guide slot 138d, and into the interior of the casing where it is formed with a concave kink 58 and then a convex kink 59 before terminating in a slightly arcuate end portion 60. This further part 50 of the connecting member 49 lies in a plane parallel to the top wall 17 which is in the same plane as the groove 54. As will be explained further for the lock, in use, it can be seen from Figures 1 and 2 that with the bolt in its fully retracted or partly extended position the kink 58 and kink 59 are spaced clear of said groove 54. However, in the fully extended position of the bolt 55 shown in Figure 3, as the deadlock element 44 pivots into the interior of the casing, the kink 58 moves into said groove. If from this position the handle 36 is now pivoted to retract the bolt 55, it can be seen that this part of the connecting member 49 is lifted at the kink 59, such that the straight part 57 of member 49 acts to move deadlock element 44 pivotally back to its Figure 1 position. Accordingly the bolt is no longer prevented from moving inwardly by element 44 and is retracted as the handle is pivoted to its Figure 5 position.

- 15 -

Figure 5 shows the position reached when the handle is in its fully pivoted position relative to the casing so that its nose part 52 engages the end wall 14, with the end portion 60 of the connecting member 49 being raised in the groove 54 to its innermost position in the casing where it lies adjacent the inner surface of the closure part 12. From these Figures it will be noted that from the inner side of the body part 45 there is a cylindrical projection 61 with a hemi-spherical head, whilst on the same axis, but at the opposite side there extends an identical but smaller diameter projection 62. This projection 62 is movable through a slot 63 in the side wall 13, and the inner surface of the side wall 13 is formed with a circular section pocket 64 around the slot 63, with a coiled compression spring 65 being received around the projection 62 and having its one end located in said pocket. In this way, the deadlock element 44 is biased to pivot inwardly into the casing, to the position shown in Figure 3, with the projection 62 acting as an indicator at the exterior of the side wall 13 of the lock to indicate whether or not the bolt 55 is deadlocked. As explained, pivoting of the handle from its Figure 3 to its Figure 5 position causes, by way of the intermediary of the connecting member 49 overcoming the force of spring 65, pivoting of the deadlock element 44 to its Figure 1 position, and accordingly, as will be explained, retraction of the bolt 55. The feature of the connecting member forms the subject of our UK Patent Application No. 0005756.2 from which our co-pending International Patent Application No. (Our Ref. 37640M) claims priority.

The housing 38 further provides a pair of spaced inwardly directed arms 66 (Figures 16 to 18 and 28) and upstanding from the inner surface of the side wall 13 are a pair of spaced parallel guide walls 67 extending normal to the

- 16 -

top and bottom walls 16,17, these guide walls 67 lying slightly inwards of the inner surface of the front wall 15, as shown schematically in Figure 16. Each guide wall is interrupted by a generally rectangular slot 67a extending inwards from the outer free edge surface of the guide wall, the two slots being aligned with each other, and also with the opening defined between the two arms 66. Moreover, the front wall of the casing is formed with a rectangular slot 68 which is in the same plane as, and thus aligned with, the aligned slots of the guide walls 67 and the opening between the arms 66. This arrangement is to accommodate a spring loaded bolt release member 69 shown in Figures 16 to 18. The member 69 is of elongate form having a tail part 70, which is straight with an upturned end, a coiled compression spring 71 being disposed around the straight section of part 70. The part 70 is arranged to engage in the opening between the arms 66, with one end of the coiled compression spring engaging against the respective sides of the arms facing the front wall 15. The other end of the spring abuts a main body part 72 of the member 69, this being arranged to slide across the guide walls 67 by being received in the slots which interrupt said guide walls as described. At the free end of the body part 72 is a chamfered nose part 73 which is arranged slidably to extend through the slot 68 as a close sliding fit, as best shown in Figures 16 and 18 which represent the fully extended and fully retracted positions respectively of the member 69. Lying between the guide walls 67 on a part cylindrical bearing surface defined between said guide walls 67, is a cylindrical bolt holding member 74 which is arranged automatically to engage with the bolt 55 in its normally fully retracted positions shown in Figures 1 and 5. The member 74 is biased by a coil spring 75 received between the top wall 17 and an end of the member 74 to move it away from the wall 17. Along its length, the member 74 is provided

- 17 -

with a transverse recess 76 in which is received the main body part 72 of the bolt release member 69. This main body part 72 is of two thicknesses joined by a chamfered surface 77 which, in this embodiment, faces the top wall 17 as shown in Figures 17 and 18. The position of this chamfered surface 77 along the length of the bolt release member 69 is such that when the member 69 is in its fully extended position shown in Figure 16, the thinner portion of the main body part 72 is within the recess 76, adjacent the side of the recess nearest the top wall 17. However, as the member 69 is extended into the casing, the chamfered surface 77 engages the edge of the recess 76 nearest the top wall 17, so that as the linear inwards movement of the bolt release member 69 continues, this chamfered surface forces the member 74 in a direction towards the top wall 17 against the bias of its spring 75. At its opposite end to that at which the spring 75 abuts, the member 74 has a pin 78 adapted to engage in a recess 79 defined in one longitudinal side of the bolt 55.

Accordingly it can now be appreciated from Figures 17 and 18 how this pin 78 of the member 74 is spring biased to engage in said recess 79, and thus to hold the bolt in its normally retracted state with the bolt release member 69 spring loaded to its fully extended position. However, as will be described, when the door 10 is closed, the member 69 is automatically forced into the casing against its spring bias, by engagement with the staple at the doorframe, so that, as the member 69 moves to its Figure 18 position, its chamfered surface 77 moves the member 74 against its spring bias to release the pin 78 from the recess 79 of the bolt 55 which then automatically moves to its extended position under the bias of a coiled compression spring (not shown) which is received in a longitudinal guide 213 which is parallel to and

- 18 -

spaced inwardly of the bottom wall 16, this guide extending upwardly from the side wall 13 and extending to the inner surface of the front wall 15. The bolt 55 is provided with a peg extending from its side facing the side wall 13, this peg extending into the guide and thus serving to compress the spring therein when the bolt is moved to its normally fully retracted position and held by member 74, release of the member 74 normally thus allowing this spring to extend in its guide, thereby moving the peg along said guide and causing extension of the bolt.

A final function provided by the housing 38 is that, in one embodiment, it is extended inwardly of its portion receiving the lock cylinder 39 and associated plug 40 to house a cylindrical component 80 having a radial blocking lug 81 extending from the outer surface thereof. If the housing 38 provides this function, then it receives part of the length of the component 80 within a cylindrical housing part which is provided with an arcuate cut-away portion therein which extends around approximately 100° of arc to allow for movement of the blocking lug 81 between its two extreme positions at opposite ends of said cut-away portion, whilst projecting outwardly from this portion of the housing 38 in which the component can rotate. For clarity, this inwardly extended part of the housing 38 is not shown in Figure 19, but is shown in Figure 28, the cut-away being indicated at 181.

The component 80 has the lug 81 extending from its outer surface adjacent one end thereof, this end being the one which is adjacent the inner end of the plug 40 as shown in Figure 19. The end surface of the plug is recessed inwardly of the end surface of the cylinder, but with a projection 82 extending beyond the end of said cylinder. The end of the component 80 is

- 19 -

formed with a reduced diameter part 83 which is sized to fit within the recess defined at the end of the cylinder, so that this end part 83 is received in engagement with the end of the plug. However this end part 83 of component 80 does itself have a recess 84 therein extending over approximately 60° of arc, with the projection 82 being received in said recess, so that when the plug is rotated by operation of a key in the plug 40 at the inside of the door this projection 82 will rotate the component 80 under some circumstances where the projection is in engagement with one of the side surfaces of the recess 84, as will be described. The provision of the recess 84 does however provide for lost motion between the plug and the component 80 so that the plug can be brought back to its position in which the key can be removed from the lock cylinder, whilst leaving the component 80 in its rotated position.

The opposite end of the component 80 has a generally central circular-section bore therein, but within said bore are a pair of diametrically opposed projections 80a (Figures 32A and 32B) of V-shape, with the respective apices of the two shaped projections being spaced apart but facing one another. The side faces of each projection are flat, and arranged so that the operating bar 28b of the plug 28a of the assembly 28 is received in this bore in such a manner that key operation of the assembly 28 from the exterior of the door will cause the bar to engage one side of one of the projections on one of its sides and one side of the other projection at its other side so as to turn this component between its opposite extreme positions (Figure 32B). The annular form and spacing of the projections means that, again, there is lost motion between the locking bar, i.e. the cylinder and plug assembly 28 and the component 80, it being appreciated that in one direction of rotation the bar

- 20 -

will engage one flat surface of one projection and one flat surface of the other projection, whilst in the other direction of rotation the bar will engage respective opposite surfaces of said projections to turn the component 80 in the other direction, again the lost motion allowing the plug and cylinder assembly 28 to be moved to a position (Figure 32A) relative to the component 80 where the key can be removed. Figures 20 to 22 and Figure 28 show schematically two small angularly spaced apart semi-circular section recesses 85,86 in the interior surface of the extended part of the housing 38 in which part of the component 80 is received, and each recess selectively mates with a small bore 87 in the exterior surface of the component 80 angularly spaced therearound from the lug 81. A small spring is received in said bore 87 and at the end of this is a small ball. In this way the ball is spring biased across the interface between the component 80 and each recess 85,86 as relative rotation takes place between the component 80 and the housing 38. In other words in each of its extreme positions, the component 80 is held substantially firmly in place, against inadvertent rotation, by the spring loaded ball.

Figure 20 shows that the handle is provided, adjacent its channel 42 with a centrally disposed projection 88 which has a flat surface which faces the closure part 12 when the handle is in its rest position shown in Figure 19. At its one side, this projection is provided with an upstanding wall 89 which acts as a stop. The position of this projection relative to the component 80 is such that under normal conditions the blocking lug 81 is in the position shown in Figure 21 or Figure 22 where it is clear of the projection 88 so that the handle can be pivoted as previously described in relation to Figures 4 and 5 to retract the bolt 55. If, however, as briefly described above, the

- 21 -

component 80 is moved angularly from its extreme position shown in Figures 21 and 22 to its other extreme position shown in Figure 20, the blocking lug 81 will lie over the flat surface of the projection 88, if the handle is in its rest position, the lug 81 engaging against the stop wall 89 as shown in Figure 20. In this position pivoting of the handle is prevented by the blocking lug 81. In relation to the handle 36, it is to be noted that a coiled torsion spring (not shown) is received around the pivot rod 41, with one end of the spring engaging against the end wall 14 and the other end engaging against the channel 42 so as to bias the handle to its rest position shown in Figure 19.

As shown in Figures 13 to 15, and also in Figures 1 to 5, the bolt 55 is of generally laminar construction being made up generally of a series of interconnected plates all defining a generally rectangular leading end part which extends into and out of the casing through a correspondingly shaped opening 91 in the front wall 15 of the casing. Defined through the centre of the bolt at a position inwards of said leading end part is a slot 92 in which is received the cylindrical projection 61 as shown in Figures 1 to 5. Whilst the two innermost and also the two outermost plates 90 defined relative to the side wall 13 terminate at the end of or shortly beyond the end of the leading end part of the bolt, the middle plate, denoted by the numeral 93, is of greater extent from said leading end part and defines two arm portions 94, 95 at opposite sides of the slot 92 which is extended to the end of the plate 93 remote from said leading end part. At the free end of the arm portion 94, part of the plate 93 is turned through 90° to form a foot 96 which is directed towards the plate 12. Similarly the free end of the arm portion 95 is also turned through 90° to provide a foot 97 again directed towards the plate 12. As will be appreciated from Figures 1 to 5 and 13 to 15, the foot 97 is for

- 22 -

engagement by the further nose part 53 to retract the bolt from its extended position, whilst the foot 97 is for engagement by a driving surface 98 of a cam 99 to be described with reference to Figures 6 to 12.

Figure 3 shows that with the bolt fully extended and the handle in its rest position, the further nose part 53 is spaced from the foot 97 of the bolt. This is to allow for the movement of the further part 50 of the connecting member 49 to its Figure 4 position by the pivoting of the handle, thereby moving the deadlock element 44 clear of the bolt, before the further nose part 53 engages foot 97 to retract the bolt. In this way, retraction of the bolt is unhindered by the element 44. Similarly Figure 6 shows that the surface 98 of the cam is spaced from the bolt foot 96 when the bolt is fully extended and the cam is in its rest position. This allows initial cam angular movement by a key, as will be described, to move the element 44 clear of the bolt (Figure 11) before the surface 98 engages the foot 96 to retract the bolt. Thus again retraction of the bolt is unhindered by the element 44.

The arm portion 94 has a hole 100 therethrough adjacent the foot 96, this hole 100 aligning, in a retracted position of the bolt, with one of the holes 12c and the holes 13b and 38d to provide access for a screwdriver shaft to one of the fixing screws 38h. In an outer edge of the other arm portion 95 is formed a circular section recess 101 which again, when the bolt is in said retracted position, aligns with the other of the holes 12c and the hole 13c and cut-away 38e, to allow screwdriver access to the other of the fixing screws 38h. In this manner with the bolt in a retracted position, and, as previously described, the assembly of lock casing part 11 and plate 12 removed from the door, the respective heads of both of these screws 38h holding the rose 110

- 23 -

are then accessible to allow the screws to be undone, in order to allow for removal of the rose, and easy replacement of the lock cylinder 39 and associated plug 40, this aspect of the invention, as mentioned, forming the subject of our UK Patent Application No. 0005753.9 and corresponding International Patent Application No. (Our Ref. 37637M). It can be arranged that the retracted position of the bolt for access to screws 38h is the one when it is held by the member 74 in Figure 17.

In an outer edge of the arm portion 94 there is provided a cut-out 102 to allow for assembly of the spring which biases the bolt outwardly, into its guide 213. Finally a circular hole 103 is provided in the arm portion 94 adjacent its end thereof nearest the leading end part of the bolt, but clear of the other four plates 90 of the bolt. In conjunction with this hole 103, there is provided in the side wall 13 a circular section through opening 104 which at the inside surface of the side wall is provided through a boss 105. Extending through said opening 104 and into said boss is a snib 106 for retaining the bolt in its normal fully retracted position as shown in Figures 13 to 15. The snib 106 has a head 107 which is visible from the exterior of the side wall 13 and which allows the snib to be manually operable from inside of the door to which the lock is fitted, in use. From the head 107, the snib is stepped downwardly twice to define a central reduced diameter part 108 and an end further reduced diameter part 109, all the parts being about a common central axis. A circlip 110 is engaged in a groove of the snib at the junction between the parts 108 and 109, and a coil spring 111 is received around the central part 108, with its one end engaged against an underside of the head 107. The snib is fitted at the opening 104 and boss 105 as shown in Figures 13 to 15, so that the other end of the spring is engaged against a step at the

- 24 -

inner part of the boss so that the snib is normally biased outwardly to its Figure 13 position where the circlip 110 acts as a stop against the innermost surface of the boss to hold the snib in place at the casing.

Although the hole 103 is of a size to receive the part 109 of the snib therein, it can be seen from Figure 13 that in its normal fully retracted state, i.e. with the nose part 52 of the handle 36 in engagement with the end wall 14, this hole 103 is out of alignment with the part 109 of the snib. However it will also be noticed that the foot 97 has itself not yet reached the inner surface of the end wall 14. Accordingly in order to operate the snib, it is first necessary to push the bolt rearwardly from its Figure 13 position by applying pressure to its leading end part. This moves the foot 97 into engagement with the inner surface of the end wall 14 as shown in Figure 14, thereby aligning the hole 103 with the part 109 of the snib, allowing the snib to be moved into said hole against its spring bias. Once the part 109 of the snib has been moved into the hole 103, the inwards pressure on the end of the bolt can then be released, and the spring acting on the bolt will move it back to its normal fully retracted position shown in Figure 15, with the part 109 of the snib retained in the hole 103, which, it will be appreciated, is somewhat oversized in relation to the diameter of the part 109 so as to allow for said movement of the bolt between its Figures 14 and 15 positions respectively. It can be seen that, if required, the free end of the part 109 can be provided with a narrow flange to define, with the circlip 110, a neck held in hole 103. Once the snib has engaged the bolt as shown in Figure 15, release of the snib can only be effected by again applying inwards pressure to the end of the bolt, thereby releasing engagement of the bolt at the edge of the hole 103 on the part 109. The spring 111 then automatically moves the released snib back to its Figure

- 25 -

13 position and the greater projection of the head 107 at the outside of the side wall 13 indicates that the snib is no longer engaged, so that in closing the door, the bolt will automatically extend as described herein above. Although as described and shown, the snib holds the bolt in its Figure 17 retracted position, the snib could alternatively be arranged to hold the bolt in a position between the positions of the bolt in Figures 13 and 15 respectively. Accordingly the hole 100 and recess 101 would be re-positioned to allow access to screws 38h, although with posi-drive screw heads a screwdriver shank at an angle thereto might still be able to undo the screws. The feature of the snib to lock the retracted bolt against release on closing the door, forms the subject of our UK Patent Application No. 0005754.7 from which our co-pending International Patent Application No. (Our Ref. 37638M) claims priority.

Finally with regard to the components of the lock, reference is made to Figures 6 to 12 which show the cam 99, the driving surface 98 of which, as mentioned previously, acts, in operation, on the foot 96 to retract the bolt 55. As will be described, the handle operates, in use, from the inside of the door to retract the bolt by way of the further nose part 53 acting on the foot 97, whereas from the outside of the door key operation at the cylinder and plug assembly 28 moves this cam 99 and thus retracts the bolt by way of the driving surface 98 engaging the foot 96. In its rest position, shown in Figures 6, 8 and 9, a side surface thereof engages a stop 99a in the form of a lug or equivalent projecting inwardly from closure part 12 to prevent anticlockwise movement of the cam (as viewed in Figure 6) from its rest position.

- 26 -

The cam 99 is provided on its one side with a hollow boss 112 (Figure 19A) which is rotatably received on the end of the component 80 which has therein the bore containing said V-shaped projections. At the other side of the cam is an upstanding boss 113 which has the same centre as the boss 112. A slot 114 for a locking bar of the cylinder and plug assembly 28 extends through the boss 113 and into the interior of the hollow boss 112, rotation of the locking bar being effected upon key rotation of the plug of the lock cylinder and plug assembly 28 to rotate the component 80 as described, with there being lost motion between the cam 99 and the component 80. As shown in Figures 6 to 12, the surface of the cam at the side at which the boss 112 is provided is formed from an edge surface 115 disposed at approximately 90° around the cam from the surface 98, with a first flat surface 116 and a second longer flat surface 117, these two flat surfaces being joined by a ramp section 118. Figures 6 and 7 show the arrangement where the bolt 55 is fully extended and deadlocked in this position by the nose 46 engaging the inner end of the plate 90 immediately adjacent the middle plate 93 at the side thereof facing the side wall 13. As shown in Figures 1 to 5 and 13 to 15, this plate which is in engagement with the middle plate 93, extends further inward than the outer plate of this side of the bolt which faces the side wall 13 so that, as shown in Figure 2, the nose 46 will also deadlock the bolt in its partly extended position, the nose then engaging the inner end of said outermost plate at this side of the bolt.

Accordingly as shown in Figure 7, corresponding to the arrangement of Figure 3, the bolt is held in its fully extended position with the hemispherical head of the projection 61 being in juxtaposition with the flat surface 116. If key operation of the lock is now effected from the exterior of the

- 27 -

door, the cam 99 will rotate as described and retract the bolt. Figure 8 shows the position where the bolt is fully retracted and held in this position by the member 74, the cam being returned by key rotation to its position shown in Figure 8, Figure 9 showing how the hemispherical head of the projection 61 is now spaced clear of the flat surface 116 as the deadlock element is now in its Figure 1 position. Figure 11 shows how the projection 61 is depressed as the cam rotates, with the head of the projection 61 being forced against its spring bias as its head engages the ramp section 118, this movement against its spring releasing the deadlocking of the bolt which can then be retracted by virtue of the driving surface 98 of the cam 99 engaging the arm portion 96 of the bolt. Figure 12 shows the relative positions of the cam and the deadlock element in the position where the cam engages the arm portion 96 before the cam is moved by key rotation to return to its Figure 8 position. With the bolt held fully retracted, key rotation will return the cam from its dashed Figure 10 position of engagement with foot 98 back to its Figure 1 position, where the cam engages its stop 99a.

Operation of the lock, in use, will now be described.

With the lock fitted to the door 10 as shown in Figure 23, the lock cylinder and plug assembly 28 is operable by a key from the outside of the door, the lock cylinder 39 and associated plug 40 of Figure 19 being operable from the inside of the door by use of the same key. Conveniently each plug and cylinder assembly, and the key, may be of the form described and claimed in our pending published European Patent Application No. 0892130.

- 28 -

Normally, with the door 10 closed, i.e. received in its associated frame, the bolt 55 is in its fully extended position, for example as shown in Figure 3, the leading end part of the bolt projecting from the front wall 15 being received in an associated keeper of any conventional form secured at or to the frame. In this state, the deadlock element 44 is in the position shown in Figure 3 where it deadlocks the bolt 55, as described, by acting as an abutment with the plate 90 of the bolt attached to the outer side of the plate 93. In this deadlocked state, the projection 62 is fully received in the case, and this provides a visual indication at the inside of the door that the deadlocking is in operation. Moreover in this state, the handle 36 is in its rest position as shown in Figure 3, the cam 99 is in its rest position as shown in Figure 6, the snib 106 is in its rest position shown in Figure 13, and the bolt release member 69 is in its retracted position shown in Figure 18, being held against its spring bias by the engagement of the nose part 73 with the surface of the staple. As can be seen from Figure 18, with the bolt release member in this position, the bolt holding member 74 is held by it clear of the adjacent side surface of the bolt.

In this deadlocked state, the door can be opened from the exterior by the use of the key for the lock in the assembly 28. If the key is inserted into the plug of the assembly 28 and turned clockwise, as viewed in Figure 20, the locking bar of the assembly 28 received in the slot 114 in the cam 99 will cause the cam to move angularly in a clockwise direction as viewed in Figures 6 to 10. Firstly the driving surface 98 of the cam will move towards the foot 96, and at the same time the ramp section 118 of the cam will engage the head of the projection 61 so as to begin moving it to release the deadlocking on the bolt, so that when the surface 98 engages the foot 96, it can begin to retract the

- 29 -

bolt into the casing as the projection 61 has now been engaged by the second longer flat surface 117 of the cam, as shown in Figure 11, with the deadlock element 44 now being clear of the outer plate 90 of the bolt, as shown in Figure 11. The cam is then moved angularly by the locking bar until the bolt is in its normally fully retracted state, shown in dashed in Figure 10, and as shown in Figure 12 with the cam moved angularly to its extreme position.

In this state, however, unless the door is now opened, the bolt is not held retracted, given that the bolt release member 69 is still in its Figure 18 position, preventing the bolt holding member 74 engaging the retracted bolt. Accordingly once the bolt is fully retracted, it is necessary to open the door, whereupon the bolt release member 69 is released from its engagement with the frame and, under its spring bias, slides to its Figure 17 position where its nose part 73 extends from the front face of the lock. This sliding allows the bolt holding member 74 to move under its spring bias, to its Figure 17 position where its pin 78 engages in the recess 79 in the side of the bolt, thereby holding the bolt in its retracted state. The key, and thus the plug of the assembly 28 can now be returned to its rest/key insertion position and the key removed. This return movement of the key brings the cam 99 from its one extreme position, shown in Figure 12 and in dashed in Figure 10, to its other extreme or rest position shown in Figure 8, with the bolt retracted, the deadlock element 44 being in the position shown in Figure 1 merely in engagement with one side of the bolt, with its projection 62 projecting from the exterior surface of side wall 13 to indicate that the bolt is not deadlocked.

Once at the inside of the door, a user can then close the door, which action automatically 'throws' the bolt, thereby locking the door. This is

- 30 -

accomplished merely by closing the door from the inside, since this will cause engagement of the nose part 73 of the bolt release member 69 with the staple, thereby forcing this member 69 into the lock casing from its Figure 17 position to its Figure 18 position, this resulting in withdrawal of the bolt holding member 74. As a consequence the bolt is automatically extended under the force of its biasing spring so that it is shot out of the casing to its Figure 3 position, with the deadlock element 44 operating automatically as shown in Figures 1 to 3 again to deadlock the bolt.

Thereafter to open the door from the inside, it is merely necessary to pivot the lever 36 at the inside of the door from its rest position shown in Figures 1 to 3 to its fully pivoted position shown in Figure 5. This pivoting of the lever is transmitted via the connecting member 49 to the deadlock element 44 so as to move this firstly to its Figure 4 position, where it no longer deadlocks the bolt, and then to its Figure 5 position where the bolt is fully retracted into the casing by virtue of the further nose part 53 of the handle engaging the foot 97 of plate 93 of the bolt as shown in Figures 4 and 5, this retraction of the bolt taking place against its biasing spring, with pivoting of the handle also taking place against its own biasing spring. Once the Figure 5 position is reached, it is again necessary to open the door in order to retain the bolt in its retracted position by means of the bolt holding member 74. Accordingly, as previously described in order to hold the bolt retracted when entering from outside, opening of the door from the inside by way of the handle will again cause the bolt release member 69 to extend out of the casing, thereby releasing the bolt holding member 74 which moves under its spring bias to engage in the recess 79 in the bolt to hold it retracted. Thereafter closing the door causes the nose part 73 of the bolt release

- 31 -

member 69 to engage the frame and be pushed inwardly, so as to move the bolt holding member 74 from its engagement with the bolt, which is thus then automatically extended out of the casing under its biasing force, so that the closed door is again automatically locked by the bolt entering into its associated keeper, the movement of the bolt from its extended to its retracted position, as shown in Figures 1 to 3, also allowing the deadlock element to move as shown in sequence through Figures 1 to 3 so as again to deadlock the extended bolt in its keeper, thereby locking the door. It will be noted from Figure 2 that due to the different lengths of the two bolt plates 90 at the side of the plate 93 facing the side wall 13, the bolt is deadlocked not only in its fully extended position shown in Figure 3, but also in its partly extended position shown in Figure 2 where the nose 46 of the deadlock element 44 engages the shorter outermost plate 93 of said two plates at said one side of the middle plate 93. This feature ensures a secondary locking position to provide security should the bolt not fully extend for any reason

An important feature of the lock of the present invention relates to the locking of the handle 36 so that it cannot be operated from the inside of the door without the key for the lock, thereby preventing an intruder exiting through the door. This feature is of particular benefit when the lock is used on glass panel doors.

To lock the door from the inside, the handle is firstly pivoted and the door opened, to hold the bolt in its retracted position. The key is then inserted into the plug 40 in its lock cylinder 39 in the housing 38. In this key insertion state, the projection 82 of the plug is against one surface of the recess 84 of the cylindrical component 80 as shown in Figure 22, with the

- 32 -

lug 81 of component 80 clear of the projection 88 of the handle, so that in this state the handle can still be pivoted. If the key is now turned in an anti-clockwise direction, as viewed in Figure 22, the plug turns, and thus the projection 82 of the plug acts on the component 80 to turn it also in an anti-clockwise direction to bring the lug 81 over the projection 88 and into engagement with the wall 89, as shown in Figure 20. During this angular movement of the component 80, the spring loaded ball associated with the component 80 moves from partial reception in the recess 86 to partial reception in the recess 85 thereby holding the component 80 in its Figure 20 position. To remove the key, it is then rotated back to its insertion position, and the lost motion between the plug and the component 80 allows the plug to rotate relative thereto, thereby bringing its projection 82 back to its original key insertion state, as shown in Figure 20. The key is then removed and the door closed on exit in the normal manner thereby automatically deadlocking the closed door as previously described. Pivoting of the handle is now prevented by the blocking lug 81.

To open the door from the outside, the key is inserted in the plug of the assembly 28 and turned in a clockwise direction as viewed in Figure 20, the locking bar 28b of this assembly 28 engaging through the cam slot 114 extending into said bore of the component 80 having said V-shaped projections 80a therein. With the cam 99 in its Figure 6 position, the disposition of the slot 114 relative to said V-shaped projections in the bore in one end of the component 80 is such that when the key is turned there is initial take-up of lost motion between the bar and respective engagement sides of the V-shaped projections, this lost motion corresponding to the movement of the driving surface 98 into engagement with the foot 96. Once this lost

- 33 -

motion has been taken up and the cam is at the position shown in full in Figure 10, continued turning of the key effects turning of the locking bar 28b, which, by virtue of its engagement with respective surfaces of the V-shaped projections 80a causes the component 80 to rotate from its Figures 20 and 32B positions to its Figures 22 and 32A positions where the lug 81 is clear of the projection 88 on the handle. This is an important safety aspect of the re-entry procedure in that it releases the locking of the handle which was effected upon original egress. As a result, once the door is thereafter closed, it can (immediately) be re-opened from the inside by pivoting the handle. The described key rotation also effects angular movement of the cam to retract the bolt as shown in Figure 10 in phantom. Again as the component 80 moves from its Figure 20 to its Figure 22 position, the spring loaded ball partly received in bore 87 moves out of partial engagement in recess 85 to partial engagement in recess 86 to hold the component 80 in its Figure 22 position. Thereafter the key is turned back to its insertion position (Figure 32B), resulting in the locking bar also moving relative to the component 80 due to the lost motion provided, so that the key can then be removed from the plug of the assembly 28 once the door has been opened and the bolt again held in its retracted position. The handle is now again operable when required to effect retraction of the bolt. It will be appreciated that with the handle blocked against angular movement, access to the fixing screw 27 for the screwdriver shank 27a through the cut-out in the end of the handle is prevented, and thus removal of the assembly of casing part 11 and plate 12 is prevented.

Finally with regard to operation of the lock, reference is made to the use of the snib 106 as shown in Figures 13 to 15.

- 34 -

As previously described, operation of the handle 36 or the cam 99 to retract the bolt 55 will bring it to the positions shown in Figures 13 and 15 respectively where the foot 97 of the plate 93 of the bolt is spaced from the interior surface of the end wall 14. In this position, as shown in Figure 13, the spring loaded snib 106 is out of alignment with the hole 103 in said plate 93, and thus cannot be operated to retain the bolt in its retracted position irrespective of the state of the bolt release member 69. However if the bolt is pushed inwardly from its leading end at the outer edge surface of the door, it can be moved to its Figure 14 position where the clearance between the foot 96 and the wall 14 is taken up so that the foot now abuts the interior surface of said wall. In this position the hole 103 has now become aligned with the snib, which can thus be pressed inwardly against its spring bias so that its end part 109 is received through said opening, removal of the inwards force on the bolt resulting in the bolt automatically being moved by its spring force in a direction to extend from the casing. However although the bolt can move by said amount of clearance away from the wall 14, further movement is stopped by the engagement of an edge of the hole 103 engaging the part 109 of the snib, as shown in Figure 15, so that the snib is held thereby to retain the bolt in its normally retracted position. The door can thus now be open and closed without the bolt automatically shooting or needing to be withdrawn.

With conventional snib locking arrangements of this type, for example where the snib is slid between engagement and non-engagement positions respectively to hold the bolt, it is possible for the snib inadvertently to be disengaged and thus allow inadvertent shooting of the bolt and resultant

- 35 -

inadvertent locking of the door. In contrast, with the present arrangement, inadvertent release of the snib is very unlikely in that specific positive action is needed at the front edge surface of the door, namely the application of pressure to the end of the bolt to force it inwardly to an extent where the hole 103 is again fully aligned with the snib which then would automatically release under its spring bias, the bolt then automatically moving to its normal retracted position. As mentioned, the snib could be arranged with the bolt, so that the bolt is held by the snib slightly inwards of its Figures 13 and 15 position, but slightly outwards of its Figure 14 position.

Finally in relation to consideration of pressure being applied to the end of the bolt, it will be noted that any attempt forcibly to retract the bolt from its Figure 3 position, for example by inserting an implement between the end of the bolt and its keeper, would result in a force being applied to the deadlock element 44. With some lock arrangements, the application of such a force to the deadlock might cause it to release from the bolt which can then be forced inwardly to unlock the door. However with the present arrangement the housing 38, as described, provides the upper half of the bearing for the rod 43 of the deadlock element. Additionally, however, this housing provides a solid wall 238 immediately adjacent the side of the rod remote from the body part 45 of the element 44. Since the housing 38 is secured to the casing by fixing screws, any inward force applied to the bolt in its Figure 3 position and received by the deadlock element 44 will be taken by said adjacent solid wall of the housing 38, and since this is securely fixed to the casing, there is resistance to disengagement of the deadlock member from its engagement with the bolt, thereby making the bolt more secure against such attack.

- 36 -

Although in the embodiment of the lock described, blocking of the handle can only be actuated from inside of the door, in an alternative embodiment means could be provided within the lock casing to allow for blocking of the handle to be actuatable from outside of the door, in addition to, or instead of, from the inside of the door. Such means could be the same as or different from the means used inside the door, and moreover whilst it would be convenient for any means operable from outside of the door to be operated by the key, so that for example the key could be used both to engage and retract the blocking member, this may not necessarily be the case, so that something other than key operation could be provided at the outside of the door to cause said blocking, and similarly something other than key operation could be provided at the inside to cause said blocking. However most preferably, the blocking would be actuatable from both inside and outside the door, preferably in both cases by means of the key of the lock.

In another embodiment means other than the outside key operation which deactivates the blocking means, such as an outer handle, could be used to retract the bolt.

CLAIMS

1. A lock for a wing movable between respective open and closed positions relative to a frame comprising a casing, a bolt operable to extend from or to retract into said casing, an operating member arranged to be operable at one side of the wing, in use, to effect retraction of the bolt, lock means arranged, in use, for key operation at the other side of the wing, and blocking means operable, in use, to prevent operation of the operating member to retract the bolt, the arrangement being such that, in use, in a locked, closed position of the wing said bolt is extended and said blocking means, if operated, prevents retraction of the bolt by said operating member, key operation of said lock means de-actuating said blocking means, if operated.
2. A lock as claimed in Claim 1, wherein the blocking means can be de-actuated from both sides of the wing.
3. A lock as claimed in Claim 1 or Claim 2, wherein the blocking means are operable from both sides of the wing to prevent operation of the operating member to retract the bolt.
4. A lock as claimed in Claim 1 or Claim 2, wherein the blocking means are operable from said one side only of the wing to prevent operation of the operating member to retract the bolt.

- 38 -

5. A lock as claimed in Claim 4, wherein the blocking means are operable to prevent operation of the operating member to retract the bolt by key operable lock means at said one side of the wing.
6. A lock as claimed in Claim 5, wherein said key operable lock means are operable at said one side of the wing to de-actuate the blocking means.
7. A lock as claimed in Claim 6, wherein the blocking means is an angularly movable cam.
8. A lock as claimed in Claim 7, wherein the operating member is a pivotable handle.
9. A lock as claimed in Claim 8, wherein the handle has a projecting surface which engages said cam when the blocking means are operated and an attempt is made to pivot the handle.
10. A lock as claimed in any one of Claims 7 to 9, wherein the cam is on a member arranged for limited angular movement by operation of said key operable lock means at said one side of the wing.
11. A lock as claimed in Claim 10, wherein an angularly movable plug of said lock means at said one side of the wing has a part received in a recess at one end of said member with lost motion between said plug and said member.

- 39 -

12. A lock as claimed in Claim 11, wherein the key of said lock means at said one side of the wing can be inserted into or withdrawn from said plug only when said plug is in a first position, angular movement of said plug in one direction from said first position to a second position operating said cam to block said operation of said operating member, with said plug then being angularly movable to said first position to take up said lost motion, and thereafter angular movement of said plug in the opposite direction from said first position to a third position de-activating said cam to remove said blocking, with the plug then being angularly movable to said first position to take up said lost motion.

13. A lock as claimed in Claim 12, wherein the cam is restrained against inadvertent angular movement in both its blocking and de-actuated states.

14. A lock as claimed in any one of Claims 11 to 13, wherein at its other end, said member defines a surface for engagement by a locking bar of said lock means for operation at the other side of the wing.

15. A lock as claimed in Claim 14, wherein in the key insertion and withdrawal position of the locking bar, with said blocking means operated, the bar is spaced angularly from said surface defined at said other end of the member, operation of an inserted key in one direction causing the bar to take up lost motion relative to said member and to engage said surface thereby to move the member angularly to de-actuate the blocking of the cam on the operating member, the bar thereafter being moved angularly by operation of the key in the opposite direction again to take up lost motion relative to said member, to return the bar to its key insertion and withdrawal position.

- 40 -

16. A lock as claimed in Claim 15, wherein the locking bar engagement surface is a composite surface defined by two side surfaces respectively of a pair of diametrically opposed V-shaped projections within a bore at said other end of the member.

17. A lock as claimed in Claim 15 or Claim 16, wherein the member mounts an angularly movable bolt drive cam and the lost motion taken up by the bar relative to the member prior to de-activation of the blocking means corresponds to movement from a rest position of the bolt drive cam in releasing means deadlocking the bolt in its extended position and engaging the bolt, so as to retract it as the blocking means are de-actuated.

18. A lock as claimed in Claim 17, wherein the lost motion taken up by the bar after de-activation of the blocking means corresponds to movement of the bolt drive cam back to its rest position from a position to where it retracts the bolt for engagement by bolt holding means.

19. A lock as claimed in any one of Claims 1 to 16, wherein said key operation of said lock means retracts the bolt.

20. A lock for a wing movable between open and closed positions relative to a frame comprising a casing, a bolt operable to extend from or to retract into said casing, an operating member at one side of the wing, in use, arranged to be pivotally operable to retract the bolt, a pivoted locking member at least partly within the casing, arranged to deadlock the bolt when

it is in its extended position, and an element providing within the casing either at least part of a bearing surface for a pivot of the operating member or a pivot of the locking member, or at least parts of respective bearing surfaces for respective pivots of the operating member and the locking member.

21. A lock as claimed in Claim 20, wherein the element provides at least parts respectively of bearing surfaces for respective pivots of the operating member and the locking member, and for each pivot, said element provides a semi-cylindrical bearing surface.

22. A lock as claimed in Claim 21, wherein each bearing surface mates with a corresponding semi-cylindrical bearing surface provided by the casing.

23. A lock as claimed in Claim 22, wherein said element has a pair of spaced, parallel arms providing respective semi-cylindrical bearing surfaces for respective opposite ends of a pivot rod for the operating member.

24. A lock as claimed in Claim 22 or Claim 23, wherein said element has a pair of spaced, parallel arms providing respective semi-cylindrical bearing surfaces for respective opposite ends of a pivot rod for the locking member.

25. A lock as claimed in Claim 24, wherein the element is secured to the casing, and a solid wall of the element is arranged immediately adjacent a side of said pivot rod for the locking member opposite from the pivot rod side at which the locking member extends.

- 42 -

26. A lock as claimed in any one of Claims 20 to 25, wherein the element provides a pair of spaced arms defining an opening therebetween, a spring biased bolt release member having a part slidably arranged in said opening, with an end of the biasing spring engaging said arms.





27. A lock as claimed in any one of Claims 20 to 26, wherein the element provides a guide slot for a spring-like connector component between the operating member and the locking member, the component operating so that via said component the locking member is released from engagement with the bolt when the operating member is pivoted to retract the bolt from its extended position.

28. A lock as claimed in any one of Claims 20 to 27, wherein the element has a portion projecting outwardly through an opening of the casing, said portion receiving a lock cylinder and plug assembly.






29. A lock as claimed in any one of Claims 20 to 28, wherein the element has at least one hole therein for fixing means securing it to said casing.

30. A lock as claimed in any one of Claims 20 to 29, wherein said element is unitary.




31. A lock as claimed in Claim 30, wherein said element is a casting.






2 / 8



3 / 8



4 / 8








FIG 20




FIG 21




FIG 22




FIG 24




FIG 23

7 / 8




FIG 25




FIG 27




FIG 28








FIG 29

8 / 8



(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
20 September 2001 (20.09.2001)

PCT

(10) International Publication Number
WO 01/69015 A3

(51) International Patent Classification⁷: E05B 13/00,
9/08, 63/00

(21) International Application Number: PCT/GB01/00735

(22) International Filing Date: 22 February 2001 (22.02.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
0005752.1 11 March 2000 (11.03.2000) GB

(71) Applicant (for all designated States except US): BAN-
HAM PATENT LOCKS LIMITED [GB/GB]; 233-235
Kensington High Street, London W8 6SF (GB).

(72) Inventor; and

(75) Inventor/Applicant (for US only): COWPER, Brian, Ed-
ward [GB/GB]; 114 Elm Road, New Malden, Surrey KT3
3HP (GB).

(74) Agents: MOSEY, Stephen, George et al.; Marks & Clerk,
Alpha Tower, Suffolk Street Queensway, Birmingham B1
1TT (GB).

(81) Designated States (*national*): AE, AG, AL, AM, AT, AU,
AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CR, CU, CZ,
DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR,
HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR,
LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ,
NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM,
TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States (*regional*): ARIPO patent (GH, GM,
KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian
patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European
patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE,
IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF,
CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).


Published:

— with international search report

(88) Date of publication of the international search report:
20 December 2001

For two-letter codes and other abbreviations, refer to the "Guid-
ance Notes on Codes and Abbreviations" appearing at the begin-
ning of each regular issue of the PCT Gazette.

(54) Title: LOCK



(57) Abstract: A lock for a door (10) comprises a cas-
ing (11), a bolt (55) operable to extend from or retract
into the casing, a pivoted operating handle (36) opera-
ble at one side of the door to retract the bolt, lock means
(28) for key operation at the other side of the door, and
blocking means (81) to prevent operation of the han-
dle to retract the bolt. In a locked closed position of
the door, the bolt (55) is extended, and with the block-
ing means operated, key operation of the exterior lock
means (28) both retracts the bolt and also de-actuates
the blocking means. At the inside of the door further
key operable lock means (39, 40) are provided solely
to operate and, if required, to de-actuate, the blocking
means.

WO 01/69015 A3

INTERNATIONAL SEARCH REPORT

International Application No
PCT/GB 01/00735

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 E05B13/00 E05B9/08 E05B63/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 E05B E05C

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EP0-Internal

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 4 709 566 A (WILDENRADT CARL H) 1 December 1987 (1987-12-01) column 1, line 16 - line 23 column 3, line 44 - line 57 column 5, line 23 - line 59; figure ---	1,2,4-6, 19
X	US 2 651 934 A (ABRAHAM E. CHESLER) 15 September 1953 (1953-09-15) column 3, line 38 -column 5, line 67; figure ---	1-3
X	US 4 563 885 A (MADDEN ROY H) 14 January 1986 (1986-01-14) column 4, line 40 -column 5, line 9; figure --- -/--	1,19

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

7 September 2001

Date of mailing of the international search report

18.09.2001

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Pieracci, A

INTERNATIONAL SEARCH REPORT

I. National Application No
PCT/GB 01/00735

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 5 794 467 A (JUSTICE RONNY E) 18 August 1998 (1998-08-18) column 4, line 19 - line 36; figure ----	1-3
A	US 4 732 418 A (CROWN MARLIN D ET AL) 22 March 1988 (1988-03-22) column 2, line 38 - line 47 column 3, line 55 -column 4, line 3; figures 3,4 ----	1,2,4
X	GB 2 268 221 A (PARKES JOSIAH & SONS LTD) 5 January 1994 (1994-01-05) page 5, line 25 -page 7, line 2; figures 3-5 ----	20,30
X	GB 2 142 688 A (BANHAM PATENT LOCKS LTD) 23 January 1985 (1985-01-23) the whole document ----	20,30
X	FR 2 626 307 A (LAPERCHÉ SA) 28 July 1989 (1989-07-28) page 4, line 33 -page 6, line 20; figure -----	20,30

INTERNATIONAL SEARCH REPORT

International application No.
PCT/GB 01/00735

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:
2. ☐ Claims Nos.:
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:
3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

see additional sheet

1. ☒ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.
2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:
4. ☐ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

Remark on Protest

- ☐ The additional search fees were accompanied by the applicant's protest.
- ☒ No protest accompanied the payment of additional search fees.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

This International Searching Authority found multiple (groups of) inventions in this international application, as follows:

1. Claims: 1-19

A lock for a wing where blocking means can be operated on one side of the wing such that retraction of the bolt by the operating member is prevented. Key operation of lock means on the other side of the wing allows retraction of the bolt and deactuation of said blocking means.

2. Claims: 20-31

A lock for a wing with a pivoting operating member on side of the wing to retract the bolt, a pivoting locking member to deadlock the bolt, and an element providing at least parts of bearing surfaces for a pivot of the operating member or of the locking member.

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/GB 01/00735

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
US 4709566	A	01-12-1987	NONE	
US 2651934	A	15-09-1953	NONE	
US 4563885	A	14-01-1986	NONE	
US 5794467	A	18-08-1998	NONE	
US 4732418	A	22-03-1988	NONE	
GB 2268221	A	05-01-1994	NONE	
GB 2142688	A	23-01-1985	NONE	
FR 2626307	A	28-07-1989	NONE	